SCHEDULE - B

Name of the Work: Formation of 6th mainroad KEGS Layout from 8th Cross to End in W-18

Tender Notification: EE/H/TEND/03/12-13 date: 02/07/2012
Item No: 07

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
1	Dismantling Mangalore tiles roof and stacking the material within a radius of 50mtrs -do- A.C. sheet roofing etc., complete as per specifications and direction of the Engineer-in-Charge	40.00	Sqm	46.00	Rupees Forty Six Only
2	Dismantling burnt brick masonry in clay mortar / lime mortar / cement mortar and stacking the bricks within a radius of 50m and removing the debris to a distance upto 200m. Conveying the excavated earth' with a lead of 10KMS etc., complete as per specifications and direction of the Engineer-in-Charge	30.24	Cum	115.00	Rupees One Hundred Fifteen Only
3	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m etc., complete as per specifications and direction of the Engineer-in-Charge	12.76	Cum	127.00	Rupees One Hundred Twenty Seven Only
4	Earthwork in excavation of foundation of structures as per drawing and technical specification including setting out, construction of shorting and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilizing the remaining earth locally for road work complete as per specifications. (i) Ordinary soil – A. Manual Means (i) Depth upto 3m. MORTH etc., complete as per specifications and direction of the Engineer-in-Charge	24.57	Cum	193.00	Rupees One Hundred Ninety Three Only
5	Providing granite slabs of 750mm roughly dressed and fixed in CM 1:6 including fixing curing etc., complete as per specifications and direction of the Engineer-in-Charge	75.60	Sqm	331.00	Rupees Three Hundred Thirty One Only
6	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clodsincluding loading & unloading, cost of labour Conveying the excavated earth to distance of upto 10kms including loading and unloading charges etc., complete as per specifications and direction of the Engineer-in-Charge	117.88	Cum	160.00	Rupees One Hundred Sixty Only

Executive Engineer (H)
Executive Engineer,
Bruhat Bangalore Mahanagara Palike
Hebbal Division,
Bruhat Bangalore Maharagara Pal...

Contractor

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
11	Providing & Laying in position reinforced cement concrete of mix 1:1.5:3 with 20mm (M-20) and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutment, pillars, posts, struts, buttresses, string or lacing course, parapets, copying, bed blocks, anchor blocks, plain windown cills, fillets etc., complete as per specifications labour HOM of machinery, curing, including cost of providing and fabricating HYSD steel 12mm tor at 15cms c/c (main) and 10mm tor at 20cms c/c (Distribution) & Providing and removing centring and shuttering et., complete as per specifications for 23cms thick drain covering slab etc., complete as per specifications and direction of the Engineer-in-Charge.	180.00	Sqm	1521.00	Rupees One Thousand Five Hundred Twenty One Only
12	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. 450 x 150 x 500mm etc., complete as per specifications and direction of the Engineer-in-Charge.	433.33	Nos	293.00	Rupees Two Hundred Ninety Three Only
13	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour etc., complete as per specifications and direction of the Engineer-in-Charge.	112.50	Sqm	49.00	Rupees Forty Nine Only

Executive Engineer (H)
Executive Engineer,
Bruhat Bangalore Mahanagara Palike
Hebbal Division,
Bruhat Bangalore Maharagara

Contractor